ENGINEERING DEPARTMENT.

BUILDINGS DIVISION, BANGALORE.

Notice dated 8th November 1938.

The public are hereby informed that the auction sale of the properties consisting of zinc sheets sheds, terraced buildings, Mangalore tiled roof buildings and trees, etc., in the premises originally occupied by the Premier Metal Factory and the White Lead Syndicate announced to be held at 9 A.M., on the 18th November 1938, is postponed to a future date to be notified later on.

B. R. GARUDACHAR,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

DEPARTMENT OF AGRICULTURE.

LIVE-STOCK SECTION.

Notification dated 3rd November 1938.

It is hereby notified for the information of the public that surplus Amrit Mahal Cattle (Male) and (Females) will be sold by public auction by the Live-Stock Expert or any other officer deputed by him on the dates and places and subject to the conditions, mentioned below:—

The sale will commence at 2 P.M. precisely on each day.

No.	Sale centre	Date	Remarks
1	Salekere ..	5th and 6th December 1938 ..	Chennagiri Taluk.
2	Holalkere ..	7th and 8th December 1938 ..	Near Holalkere Railway Station.
3	Dudda ..	9th and 10th December 1938 ..	Hassan Taluk.

1. The sale shall be knocked down in favour of the person who offers the highest bid, provided the Live-Stock Expert or the officer conducting the sale does not consider it unreasonably low. As soon as the sale is concluded, the purchaser shall pay 25 per cent of the sale amount and furnish suitable security for the balance. The balance shall be paid by him within three days from the date of sale, failing which the animal shall be resold at the risk of the original purchaser. Any loss that may accrue on such resale, shall be recoverable from him as arrears of land revenue, but he shall not be entitled to participate in the event of any profits. The animal, till then, will be retained by the Department at the risk of the purchaser.

2. Persons whose solvency may be considered to be doubtful, may be required by the officer conducting the sale at his discretion, to deposit from Rs. 10 to Rs. 25 so as to ensure their *bona fides* at the time of bidding.

3. Withdrawal or takarar of any kind will not be considered once the bid is offered in open sale and concluded and the final record of the sale in the register and signing thereof by the purchaser (which is compulsory) or in case the party refuses to sign, a note to this effect by the officer conducting the sale shall be tantamount to acceptance of all liabilities imposed in sale conditions.

A. A. MONTEIRO, LIEUT,
Live-Stock Expert.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notification dated 7th November 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, upto 1 P.M. on 18th November 1938, for leading the sewage from the present terminal of the ovoid sewer to the open flood water drain in Bangalore City. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1938.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,000 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for leading the sewage from the present terminal of the ovoid sewer to the open flood water drain in Bangalore City," in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Director of Public Health who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Director of Public Health will be final and legally binding.

12. The Department is not bound to give the whole work to the contractor who tenders lowest rates. In the interest of quick execution of work it may be splitted into different portions and distributed amongst two or more contractors at the lowest tendered rates.

Approximate estimate of quantities of work for leading the sewage from the present terminal of the ovoid sewer to the open flood water drain in Bangalore City.

No.	Items of work	Unit	Quantity
1	Earthwork excavation and refilling and consolidating including water bailing, shoring barricading, etc.	C.yd.	2,880
2	Laying 15" dia. old steel pipes over 1' of sand bed including jointing with hemp and cement or molten lead and including carting pipes to site (pipes being supplied departmentally) pipes laid in 2 rows 2×1620	R.ft.	3,240–
3	Constructing rectangular inspection and cleaning chambers 5'×4'×12' each with wire cut bricks in cement mortar 1 : 4 and cement plastering, fixing C.I. steps and manhole covers with frame 4 cwts. each ..	No.	6
4	Regarding the existing flood water drain from the road dam to Sunnakal tank bund	R.ft.	3,000
5	Constructing detritus chamber	As per	data.
6	Constructing screening chambers	As per	data.
7	Deepening the septic tank chamber if necessary and for installing pumping plant and repairs	As per	data.

N.B.—Proportions for—

1. Cement concrete 1 : 2½ : 5.
2. Cement mortar plastering 1 : 2.
3. Cement mortar for brick masonry 1 : 4.

N. KRISHNIENGAR,
Sanitary Engineer.

GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

OFFICE OF THE CHIEF ELECTRICAL ENGINEER, BANGALORE.

Notification No. G. N. 33, dated 7th November 1938.

To

The Firms dealing in Fuse-wires, etc.

DEAR SIRS,

Please quote your best billing prices for the following fuse-wires to be delivered f.o.r., Bangalore :—

(1)	Fuse wire of alloyed lead,	½ amp.	3 lbs.
(2)	Do	1 amp.	7 lbs.
(3)	Do	3 amps.	50 ,,
(4)	Do	5 ,,	50 ,,
(5)	Do	10 ,,	50 ,,
(6)	Do	15 ,,	50 ,,
(7)	Do	20 ,,	50 ,,
(8)	Do	30 ,,	50 ,,
(9)	Fuse wire of tinned copper	50 amps.	25 lbs.